

**German Embassy School - Sports field extension VOLLEYBALL FIELD**

No.	Description	Unit	Qty	Rate	Amount
				(ETB)	(ETB)
<b>1,0</b>	<b>Mobilization: Transport cost</b>				
1,1	Delivery and collection of machinery, like excavator, compactor, fuel, or any other.	1	flat		0,00
<b>2,0</b>	<b>Surveying</b>				
2,1	Surveying, marking out and determining heights according to the plan and in consultation with the client	1	flat		0,00
<b>3,0</b>	<b>Earthwork: Excavation and Leveling</b>				
3,1	Excavation of ground for field 14 x 22m, about 50cm deep	m2	308		0,00
3,2	Load and carry away ground material from excavation	m3	154		0,00
3,3	Level ground in excavated pit	m2	308		0,00
<b>4,0</b>	<b>Foundation for Volleyball-Net Post</b>				
4,1	Build in foundation for volleyball-net posts at defined position below drainage layer; dimension 80x80x80 cm concrete cube; Concrete C12/15	pcs.	2		0,00
<b>5,0</b>	<b>Drainage layer</b>				
5,1	Deliver gravel (crushed stone without powder content) for a drainage substructure	m3	15,5		0,00
5,2	Level gravel (crushed stone without powder content) evenly; about 5 cm thick layer	m2	308		0,00
5,3	Cover the gravel substructure with water-permeable geotextile (material provided by the school)	m2	308		0,00
<b>6,0</b>	<b>Construction: Concrete work</b>				
6,1	Build in curbstone (e.g. Bazola vertically built in above geo-textile) at the perimeter of the sandpit in concrete; 5 cm below the end-height to prevent injuries; Concrete C12/15	m	72		0,00

<b>7,0</b>	<b>Play Sand</b>				
7,1	Deliver sieved sand; particle size < 1.5 mm; bright (white) color (Akaki?)	m3	140		0,00
7,2	Fill and level sand in the pit	m2	308		0,00

Total					0,00
VAT					0,00
Total with VAT					0,00

